




**Henry County Board of Commissioners  
Purchasing Department  
140 Henry Parkway, McDonough, GA 30253**

**Phone: 770-288-6027**

**Fax: 770-288-6047**

**Website: [www.co.henry.ga.us/Departments/M-R/PurchasingDepartment.aspx](http://www.co.henry.ga.us/Departments/M-R/PurchasingDepartment.aspx)**

*Rod Gray* 

Rod Gray, Director of Purchasing

**ADDENDUM #1**

**Issued June 22, 2017**

**BID # 17-54**

**Grading, Widening, and Paving of Turner Church Road**

**OPENING: 3:00 PM, June 29, 2017**

---

The following items take precedence over referenced portions of the documents for the above-named project and in executing a contract, will become a part thereof.  
Where any item in the documents is supplemented hereby, the original requirements will remain in effect. All supplemental conditions will be considered as added thereto.  
Where any original item is amended, voided or superseded hereby, the provisions of such items not so specifically amended, voided or superseded will remain in effect.

---

This addendum must be signed and attached to bid proposal to acknowledge receipt of addendum.  
**Failure to acknowledge any addenda will result in a non-responsive bid.**

\_\_\_\_\_  
Company's Name

\_\_\_\_\_  
Date

\_\_\_\_\_  
Authorized Representative's Name

\_\_\_\_\_  
Authorized Representative's Signature

**Bid #17-54**  
**Grading, Widening, and Paving of Turner Church Road**  
**Questions and Answers**

1. **Question:** On the Storm Drain Profiles you show a Line of Pipe A1 to A2 to A3 (approximately 300 LF) however this line of pipe is not shown on Mainline Plan Sheet 13-04 at this location. Can you clarify if it is truly required?

**Answer:** **The pipe and structures A1, A2 and A3 have been removed and the mainline plans are showing the correct design. Quantities will be adjusted.**

2. **Question:** We believe you have some quantity issues that you may want to correct:

Bid Item	Henry Co Qty	CWM Qty	Difference
Graded Aggr Base	6,100 Tons	4,597 Tons	Overstated 32.7%
Recy Asph Conc 19.0mm	1,634 Tons	1,871 Tons	Overstated 14.5%

**Answer:** **Quantities are adjusted as follows:**  
**Graded Aggr Base = 5,200 tons**  
**Recy Asph Conc 19.0mm = 1900 tons**

3. **Question:** On plan sheet 22-01 you show Structure B-2 as some type of Outlet Control Structure for the pond located on the Right Side @ 45+50, however you do not have a bid item for this Outlet Control Structure. Should we assume that this will be priced out and added by Supplemental Agreement later? On sheet 04-02, upper right corner of the sheet, you tell us it will be paid for as a Catch Basin Gp 1 Special Design but this item is not included in the bid form.

**Answer:** **Please see revised sheet 04-02. Also construction of pond shall be included in Grading Complete line item.**

4. **Question:** On plan sheet 04-02 you show Outlet Control Structure as being B-3, I believe this should be Structure B-2 as B-3 is shown as a pair of 18" FES coming into the pond.

**Answer:** **Please see revised sheet 04-02.**

5. **Question:** Will Rock Excavation be paid for?

**Answer:** **All encounter rock excavation during the construction shall be included in the overall bid of Grading Complete line item.**

6. **Question:** If Rock Excavation will not be paid for if encountered, Is access available to the entire project for the purposes of drilling / digging to determine how much rock is onsite?

**Answer:** **Contractor can only drill within the existing road. Contractor is responsible in calling 811 before drilling.**

**Bid # 17-54**  
**Grading, Widening, and Paving of Turner Church Road**  
**Bid Price Sheet (Revised)**

LINE NO.	ITEM NO.	ITEM DESCRIPTION ROADWAY	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0005	150-1000	TRAFFIC CONTROL - SP 4335	LS	1		
0010	210-0100	GRADING COMPLETE - SP 4335	LS	1		
0015	310-1101	GR AGGR BASE CRS, INCL MATL	TN	5200		
0020	318-3000	AGGR SURF CRS	TN	2000		
0025	402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	938		
0030	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1900		
0035	413-1000	BITUM TACK COAT	GLF	933		
0040	441-0014	DRIVEWAY CONCRETE, 4 IN	SY	146		
0045	441-0014	CONC SPILLWAY, SPCL DESIGN	EA	1		
0050	550-1060	STORM DRAIN PIPE, 6 IN, H 1-10	LF	4		
0055	550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	LF	44		
0060	550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	200		
0065	550-1180	SIDE DRAIN, 18 IN, H -10	LF	112		
0070	550-4215	FLARED END SECTION, 15 IN, STORM DRAIN	EA	2		
0075	550-4218	FLARED END SECTION, 18 IN, STORM DRAIN	EA	12		
0080	643-8000	GATE FIELD FENCE	EA	6		
0085	643-8104	BARBED WIRE FENCE, 4 STRANDS (TEMPORARY)	LF	2850		
0090	643-8105	BARBED WIRE FENCE, 5 STRANDS	LF	3500		
0095	643-8405	SPECIAL DESIGN, ELECTRIC FIELD FENCE, 5 STRAND WITH FIBERGLASS LINE POSTS	LF	5200		
<b>SUBTOTAL (ROADWAY)</b>						
LINE NO.	ITEM NO.	ITEM DESCRIPTION SIGNING & MARKING	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0100	636-1033	HIGHWAY SIGNS, TPI MATL, REFL. SHEETING TP 9	SF	14		
0105	636-1036	HIGHWAY SIGNS, TPI MATL, REFL. SHEETING TPI1	SF	42		
0110	636-2070	GALV STEEL POSTS, TP 7	LF	68		
0115	653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	7260		
0120	653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	7250		

Company's Name: \_\_\_\_\_

**Bid # 17-54**  
**Grading, Widening, and Paving of Turner Church Road**  
**Bid Price Sheet (Revised)**

LINE NO.	ITEM NO.	ITEM DESCRIPTION SIGNING & MARKING (CONTINUED)	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0125	653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	80		
0130	654-1001	RAISED PVMT MARKERS TP 1	EA	90		
<b>SUBTOTAL (SIGNING &amp; MARKING )</b>						
LINE NO.	ITEM NO.	ITEM DESCRIPTION EROSION CONTROL	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0135	163-0232	TEMPORARY GRASSING	AC	3		
0140	163-0240	MULCH	TN	95		
0145	163-0300	CONSTRUCTION EXIT	EA	3		
0150	163-0527	CONSTRUCT CHECK DAM	EA	52		
0155	163-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	EA	2680		
0160	165-0041	MAINTENANCE OF ALL CHECK DAMS – ALL TYPES	LF	52		
0165	165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	3		
0170	167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	2		
0175	167-1500	WATER QUALITY INSPECTIONS	MO	11		
0180	171-0030	TEMPORARY SILT FENCE, TYPE C	LF	2680		
0185	603-2018	STN DUMPED RIP RAP, TP 1, 18 IN	SY	25		
0190	603-7000	PLASTIC FILTER FABRIC	SY	25		
0195	700-6910	PERMANENT GRASSING	AC	5		
0200	700-7000	AGRICULTURAL LIME	TN	10		
0205	700-8000	FERTILIZER MIXED GRADE	TN	4		
0210	700-8100	FERTILIZER NITROGEN CONTENT	LB	238		
<b>SUBTOTAL (EROSION CONTROL)</b>						
<b>TOTAL BID AMOUNT</b>						

\_\_\_\_\_

**TOTAL BID AMOUNT (WORDS)**

\_\_\_\_\_

Company's Name

\_\_\_\_\_

Date

\_\_\_\_\_

Authorized Representative's Name (Print or Type)

\_\_\_\_\_

Authorized Representative's Signature