



**Henry County Board of Commissioners
Purchasing Department**

140 Henry Parkway, McDonough, GA 30253

Phone: 770-288-6027

Fax: 770-288-6047

Website: www.co.henry.ga.us/Departments/M-R/PurchasingDepartment.aspx

Rod Gray

Rod Gray, Director of Purchasing

ADDENDUM #1

Issued November 8, 2017

BID # 18-16

Grading, Widening, and Paving for Elliott Road

OPENING: 3:00 PM, November 15, 2017

The following items take precedence over referenced portions of the documents for the above-named project and in executing a contract, will become a part thereof.

Where any item in the documents is supplemented hereby, the original requirements will remain in effect. All supplemental conditions will be considered as added thereto.

Where any original item is amended, voided or superseded hereby, the provisions of such items not so specifically amended, voided or superseded will remain in effect.

This addendum must be signed and attached to bid proposal to acknowledge receipt of addendum.

Failure to acknowledge any addenda will result in a non-responsive bid.

Company's Name

Date

Authorized Representative's Name

Authorized Representative's Signature

**Bid #18-16, Grading, Widening, and Paving for Elliott Road
Questions and Answers**

- 1. Question:** In the Supplemental Provisions # 18 (page 18 of 37) tells us that Variable Message Boards are required for the Road Closure. However we have not been able to find any road closure plans or any restrictions as to how long the road can be closed. Can you please provide more information regarding the road closure such as how long the road can be closed, what the offsite detour route is that you want to use during the closure and what are the limits of where the road can be closed?

Answer: **The contractor shall provide a detour plan for any road closure on this project. Up to 2 months of closure is allowed.**
- 2. Question:** You have a bid item for (500-3200) Class B Concrete – 12 CY which we presume is for the Headwalls. Typically these headwalls require rebar, how do you intend to pay for rebar?

Answer: **The bid item (500-3200) Class B Concrete has been changed to Class B Concrete, incl Reinf Steel.**
- 3. Question:** What is your expected Notice to Proceed date for this project?

Answer: **Expected NTP will be issued 2 weeks after Henry County Board of Commissioners approval of bid #18-16.**
- 4. Question:** In regards to the project above, have an estimated budget and start date been established and are there any union requirements?

Answer: **The project budget will not be provided. Construction start date has not been established. There is no union requirement for this project.**
- 5. Question:** Can you please explain the Supplier Inclusion Program in greater detail. Are only prime contractors required to fill out this form or should it be completed by all subs and suppliers pricing us work?

Answer: **Only prime contractors should fill out this form and the Supplier Inclusion Program will only track the information provided on the form.**
- 6. Question:** How should the ‘Supplier Inclusion Program’ form be filled out? Is it only applicable to the Prime Contractor, if they qualify for one of the categories? Or should each applicable category be checked if the Prime Contractor lists a Subcontractor on the ‘List of Subcontractors’ form?

Answer: **Only prime contractors should fill out this form.**
- 7. Question:** This project has some large cuts and fills, and the majority of the cuts & fills are within the footprint of the existing Elliott Rd. Is the ‘Aggregate Surface Course’ quantity intended to cover all work necessary to keep access to East Lake Rd and Crumbly Rd for the homeowners during the entire construction duration? If this quantity overruns significantly to keep access during the construction, will Henry County pay the additional Tons necessary?

Answer: **Aggregate Surface Course is intended for inclement weather. It is not intended to cover all of the project unless directed by the County engineer.**
- 8. Question:** Please confirm that all the existing property fences that need to be replaced, regardless of what type of fence is existing, will be paid under Bid Item ‘Field Fence Woven Wire’.

Answer: **Please see updated pay item.**
- 9. Question:** Please provide a schedule for the relocation of the Overhead power and communication lines.

Answer: **Utility relocation schedule will be provided during pre-construction meeting at a later date.**

Bid # 18-16
Grading, Widening, and Paving for Elliott Road
Bid Price Sheet (Revised)

1 of 3

LINE NO.	ITEM NO.	ROADWAY	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0005	150-1000	TRAFFIC CONTROL - SP4430	LS	1		
0010	207-0203	FOUND BKFILL MATL, TP II	CY	87		
0015	210-0100	GRADING COMPLETE - SP4430	LS	1		
0020	310-1101	GR AGGR BASE CRS, INCL MATL	TN	8,100		
0025	318-3000	AGGR SURF CRS	TN	1,700		
0030	402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	1,700		
0035	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	3,000		
0040	413-0750	TACK COAT	GL	1,200		
0045	441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	430		
0050	441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	3,000		
0055	444-1000	SAWED JOINTS IN EXIST PAVEMENTS - PCC	LF	44		
0060	500-3101	CLASS A CONCRETE	CY	320		
0065	500-3200	CLASS B CONCRETE, INCL REINF STEEL	CY	12		
0070	511-1000	BAR REINF STEEL	LB	31,000		
0075	550-1300	STORM DRAIN PIPE, 30 IN, H 1-10	LF	59		
0080	550-1481	STORM DRAIN PIPE, 48 IN, H 10-15	LF	200		
0085	550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	1,400		
0090	550-2240	SIDE DRAIN PIPE, 24 IN, H 1-10	LF	80		
0095	550-3330	SAFETY END SECTION 30 IN, STORM DRAIN, 4:1 SLOPE	EA	1		
0100	550-3418	SAFETY END SECTION 18 IN, SIDE DRAIN, 4:1 SLOPE	EA	24		
0105	550-3424	SAFETY END SECTION 24 IN, SIDE DRAIN, 4:1 SLOPE	EA	1		
0110	550-3618	SAFETY END SECTION 18 IN, SIDE DRAIN, 6:1 SLOPE	EA	24		
0115	550-3624	SAFETY END SECTION 24 IN, SIDE DRAIN, 6:1 SLOPE	EA	1		
0120	603-2024	STN DUMPED RIP RAP, TP 1, 24 IN	SY	150		
0125	603-2181	STN DUMPED RIP RAP, TP 3, 18 IN	SY	220		
0130	603-7000	PLASTIC FILTER FABRIC	SY	370		
0135	610-9099	REM WINGWALLS & PARAPETS, STA - 151+86 LT & RT	LS	1		

Company's Name: _____

Bid # 18-16
Grading, Widening, and Paving for Elliott Road
Bid Price Sheet (Revised)

2 of 3

LINE NO.	ITEM NO.	ROADWAY (CONTINUED)	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0140	641-1200	GUARDRAIL, TP W	LF	1,800		
0145	641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	6		
0150	641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	6		
0155	643-0010	FIELD FENCE WOVEN WIRE (WITH 2 STRANDS BARBED WIRE ON TOP)	LF	3,500		
0160	643-0050	TEMPORARY FIELD FENCE (WOVEN WIRE)	LF	1,000		
0165	643-0050	TEMPORAY FIELD FENCE (5 STRANDS BARBED WIRE)	LF	3,700		
0170	643-8103	BARBED WIRE FENCE, 3 STRAND (WITH WOOD POST)	LF	400		
0175	643-0105	FIELD FENCE BARBED WIRE, 5 STRANDS	LF	3,700		
0180	643-8000	GATE, FIELD FENCE	EA	9		
0185	668-4300	STORM SEWER MANHOLE, TP 1	EA	2		
SUBTOTAL (ROADWAY)						
LINE NO.	ITEM NO.	PERMANENT EROSION CONTROL	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0190	700-6910	PERMANENT GRASSING	AC	11		
0195	700-7000	AGRICULTURAL LIME	TN	33		
0200	700-8000	FERTILIZER MIXED GRADE	TN	12		
0205	700-8100	FERTILIZER NITROGEN CONTENT	LB	600		
0210	716-2000	EROSION CONTROL MATS, SLOPES	SY	13,000		
SUBTOTAL (PERMANENT EROSION CONTROL)						
LINE NO.	ITEM NO.	TEMPORARY EROSION CONTROL	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0215	163-0232	TEMPORARY GRASSING	AC	6		
0220	163-0240	MULCH	TN	200		
0225	163-0300	CONSTRUCTION EXIT	EA	4		
0230	163-0502	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 2	EA	3		
0235	163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	4		
0240	163-0527	CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	EA	148		
0245	163-0528	CONSTRUCT AND REMOVE FABRIC CHECK DAM - TYPE C SILT FENCE	LF	3,920		
0250	165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	3,200		

Company's Name: _____

Bid # 18-16
Grading, Widening, and Paving for Elliott Road
Bid Price Sheet (Revised)

3 of 3

LINE NO.	ITEM NO.	TEMPORARY EROSION CONTROL (CONTINUED)	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0255	165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	2,000		
0260	165-0041	MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	3,440		
0265	165-0086	MAINTENANCE OF SILT CONTROL GATE, TP 2	EA	3		
0270	165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	4		
0275	165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	4		
0280	167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	4		
0285	167-1500	WATER QUALITY INSPECTIONS	MO	16		
0290	171-0010	TEMPORARY SILT FENCE, TYPE A	LF	6,300		
0295	171-0030	TEMPORARY SILT FENCE, TYPE C	LF	4,000		
0300	643-8200	BARRIER FENCE (ORANGE), 4 FT	LF	1,200		
SUBTOTAL (TEMPORARY ROSION CONTROL)						
LINE NO.	ITEM NO.	SIGNING & MARKING	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0305	636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	10		
0310	636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	SF	25		
0315	636-2070	GALV STEEL POSTS, TP 7	LF	80		
0320	653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	13,000		
0325	653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	12,000		
0330	653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	44		
0335	654-1001	RAISED PVMT MARKERS TP 1	EA	300		
SUBTOTAL (SIGNING AND MARKING)						
TOTAL BID AMOUNT						

TOTAL BID AMOUNT (WORDS)

 Company's Name

 Date

 Authorized Representative's Name
 (Print or Type)

 Authorized Representative's Signature