



Henry County Board of Commissioners
Purchasing Department
140 Henry Parkway, McDonough, GA 30253
Phone: 770-288-6027 Fax: 770-288-6047
Website: www.co.henry.ga.us/Departments/M-R/PurchasingDepartment.aspx

Rod Gray Rod G

Rod Gray, Director of Purchasing

ADDENDUM #3
Issued February 9, 2018

Bid #18-20
Improvements to Crack Seal and Remark Apron Pavement at the Henry County Airport
OPENING: 3:00 PM, February 16, 2018

The following items take precedence over referenced portions of the documents for the above-named project and in executing a contract, will become a part thereof. Where any item in the documents is supplemented hereby, the original requirements will remain in effect. All supplemental conditions will be considered as added thereto. Where any original item is amended, voided or superseded hereby, the provisions of such items not so specifically amended, voided or superseded will remain in effect.

This addendum must be signed and attached to bid proposal to acknowledge receipt of addendum.
Failure to acknowledge any addenda will result in a non-responsive bid.

Company's Name

Date

Authorized Representative's Name

Authorized Representative's Signature

ADDENDUM NO. 3

TO

**CONTRACT DOCUMENTS AND SPECIFICATIONS
FOR IMPROVEMENTS FOR THE
CRACK SEAL AND REMARK APRON PAVEMENT**

**AT THE
HENRY COUNTY AIRPORT
HAMPTON, GEORGIA**

Croy Engineering, LLC Project 1580.02

Date Addendum Issued:
February 9, 2018

Bid Date:
February 16, 2018

TO ALL BIDDERS: The original contract documents for the above reference project (issued for bid, dated August 22, 2017) are amended as noted herein. This Addendum hereby becomes a part of said contract documents. Acknowledge receipt of this Addendum in the space provided on Page 22. Insofar as those documents are at variance with this Addendum, this Addendum will govern.

Clarifications:

1. **Question:** RE: 620-3.6 Test strip, Could you please clarify how they would like the paint to be applied on the Henry County jobs? It does not have a temporary coat listed on the chart but below mentions a 50% first coat and 100% second coat?

Answer: No temporary paint will be applied. Paint shall be applied to the pavement with a marking machine from two directions at 50% with no glass beads in the first direction, and at 100% with glass beads in the other direction. The Contractor may apply one coat of paint in a single application as long as the specifications are met.

2. **Question:** Per Section 1510 Temporary Facilities, 1.05 Temporary Water states that the site is served by a well owned by the Airport Owner. What is the cost of the water used by the contractor?

- a. Where on the site will the contractor be able to get the water from- please show on location map?
b. Is there any limits to the amount of water that may be taken for the construction- maximum MG per day?

Answer: Water will be furnished by the Contractor. The statement in regards to the well onsite has been removed. See Section 01510.

3. **Question:** What is the anticipated date for start of construction- NTP?

Answer: Within one-hundred and twenty (120) days from the date of the bid opening.

4. **Question:** The stated contract time for construction is 30 Calendar days. Per the revised Division 7 –FAA Special Provision Section 605 (per Addendum #1), Soil Sterilization

Henry County Airport

must be applied 20 days prior to crack seal work, then 10 days the second application is applied. With the project split into 3 phases which must be completed in order – is the 30 calendar days realistic?

Answer: The clock can be stopped during the waiting period.

- 5. Question:** Per page 64 of the specifications document, must the bidding contractor request a special set of proposal forms or will filling out the forms from the website suffice?

Answer: All Henry County forms and Croy forms listed in Addendum #2 must be completed.

Remove and Replace the following:

Section 01510: Temporary Facilities (page 01510-1)

**END OF ADDENDUM NO. 3
THIS ADDENDUM MUST BE ACKNOWLEDGED IN BID**

SECTION 01510

TEMPORARY FACILITIES

1.01 DESCRIPTION:

- A. Contractor shall furnish, install and maintain temporary facilities required for construction; remove on completion of Work.
- B. Related requirements specified in other sections: The respective Sections of the Specifications.

1.02 REQUIREMENTS OF REGULATORY AGENCIES:

- A. Comply with national electric code.
- B. Comply with Federal, State, and Local codes and regulations and with utility company requirements.

1.03 MATERIALS - GENERAL:

- A. Materials may be new or used, but must be adequate in capacity for the required usage, must not create unsafe conditions, and must not violate requirements of applicable codes and standards.

1.04 TEMPORARY ELECTRICITY AND LIGHTING:

- A. Provide temporary electrical service required for power, lighting, and field offices, and pay all costs for service and for power used.

1.05 TEMPORARY WATER:

- A. Provide water for construction purposes; pay all costs for installation, maintenance and removal, and service charges for water used.
- B. The Contractor shall provide and pay all costs for water required for the performance of the work.

1.06 TEMPORARY SANITARY FACILITIES:

- A. Provide sanitary facilities in compliance with laws and regulations.
- B. Service, clean and maintain facilities and enclosures.

1.07 TEMPORARY SUPPORT FACILITIES:

- A. General: Provide a reasonably neat and uniform appearance in temporary Support Facilities acceptable to the Engineer and the Owner.
- B. Locate field offices, storage and fabrication sheds and other support facilities for easy access to the Work. Position offices so that windows give the best possible view of

- construction activities.
- C. Maintain field offices, storage and fabrication sheds, temporary sanitary facilities, waste collection and disposal systems, and project identification and temporary signs until near substantial completion. Immediately prior to substantial completion remove these facilities.
- D. Access Roads:
1. Location of access roads will be approved by the Engineer and will be set to minimize conflict with the Airport operations and shall be maintained, be well defined and be confined to the minimum area required.
 2. The Contractor shall construct the access roads and shall maintain the roads as required to create no dust. All project traffic must be routed through these areas. The Contractor shall provide all markings required to clearly define the access roads.
 3. The Contractor may be required to obtain driveway permits for certain access roads. If access roads cross a utility, the Contractor shall protect the utility as directed by the owner of the utility.

1.08 EXECUTION - GENERAL:

Maintain and operate systems to assure continuous service.

1.09 REMOVAL:

Completely remove temporary materials and equipment when their use is no longer required. Clean and repair damage caused by temporary installations or use of temporary facilities.

2.01 MEASUREMENT AND PAYMENT:

There will be no separate measurement and payment for work specified in this Section.

END OF SECTION 01510