

**Bid #19-07
Guardrail Repairs
Bid Tabulation**

Item No.	Locations	E& D Contracting Services Savannah, GA	Martin-Robbins Fence Co. Snellville, GA	Stembridge Custom Metals Fairburn, GA
1	Eagle's Landing Pkwy (Eastbound at 471): Remove and replace Tp 12 Anchor – keep existing guardrail height of 27".	\$8,000.00	\$4,995.00	\$4,830.00
2	East Lake Pkwy (Westbound east of Henry County Water Authority property), 33.5164, -84.1588: Replace 2 damaged posts and 2 -25' sections of W-Beam Guardrail (keep existing guardrail height).	\$5,500.00	\$4,400.00	\$1,700.00
3	East Lake Pkwy (Westbound east of Springdale Rd), 33.5199, -84.1655: Remove and replace Tp 12 anchor, 1 section (25LF) of guardrail, and 2 damaged posts (keep existing guardrail height of 27").	\$10,000.00	\$6,398.00	\$5,820.00
4	East Lake Pkwy (Westbound, across from 5040 East Lake Pkwy), 33.5187, -84.1631: Remove and replace 50LF of W-Beam Guardrail including Tp 1 anchor. Place new W-Beam guardrail at 31" height and within the 50 LF section provide a 31" o 27" transition to existing per GDOT Standard 4390.	\$8,500.00	\$6,434.00	\$6,184.00
5	East Lake Pkwy (Eastbound, west of Springdale Rd), 33.5203, -84.1771: Straighten or replace 4 posts, and replace 2 -25' sections of W-Beam guardrail (keep existing guardrail height of 27")	\$7,500.00	\$4,100.00	\$2,200.00
6	East Lake Pkwy (Eastbound, near 5040 East Lake Pkwy), 33.5188, -84.1633: Remove and Replace Tp 12 Anchor (27" Height).	\$8,000.00	\$4,995.00	\$4,989.00
7	North Ola Rd (Walnut Creek Bridge): Repair/replace existing Tp 1 Anchor on SW quadrant and replace terminal piece on Tp 12 Anchors in SE Quadrant and NW Quadrant.	\$8,000.00	\$5,780.00	\$3,250.00
8	Oak Grove Rd (Crittle Creek Bridge): Northwest Quadrant – Replace all existing guardrail and Tp 12 Anchor from north end of T-Beam thru the Tp 12 Anchor. All new guardrail placement and Tp 12 anchor to be at 31" height and is to include the T-Beam to W-Beam transition.	\$17,000.00	\$9,547.00	\$6,349.00
9	Oak Grove Rd (Crittle Creek Bridge): Southwest Quadrant – Replace existing guardrail from south end of T-Beam thru the Tp 1 Anchor. All new guardrail placement and Tp 1 anchor to be at 31" height and is to include the T-Beam to W-Beam transition.	\$19,000.00	\$6,509.00	\$5,399.00
9	Old Conyers Rd (James Creek Bridge): Replace damaged existing guardrail in kind. 25LF of W-Beam Guardrail and 4 posts (1 posts attached to bridge concrete curb)	\$5,500.00	No Bid	\$2,975.00
10	East Atlanta Rd (Big Cotton Indian Creek Bridge), 33.5700, -84.2324: Northeast Quadrant – Replace 3 posts and 2 – 25' sections of W-Beam guardrail (keep existing height of 27").	\$7,000.00	\$4,735.00	\$2,725.00
11	Turner Church Rd (Camp Creek Bridge), 33.4746, -84.1327: In northwest quadrant of bridge, remove existing portion of Tp 12 Anchor (at old driveway opening location) and portion of guardrail back to west end of T-Beam. Replace approximately 80' of guardrail including the Tp 1 anchor – all new guardrail to be at 31" height and is to include the T-Beam to W-Beam transition.	\$24,000.00	\$7,443.00	\$8,090.00
Total		\$128,000.00	\$65,336.00	\$54,511.00