



**Henry County
Purchasing Department**
140 Henry Parkway, McDonough, GA 30253
Phone: 770-288-6027 Fax: 770-288-6047

Website: henrycounty-ga.com/purchasing

ADDENDUM #2
Issued April 12, 2019

Bid #19-33
Cement Stabilized Base Reclamation Construction, Milling & Resurfacing on Various County Roads
OPENING: 3:00 PM, April 17, 2019

The following items take precedence over referenced portions of the documents for the above-named project and in executing a contract, will become a part thereof. Where any item in the documents is supplemented hereby, the original requirements will remain in effect. All supplemental conditions will be considered as added thereto. Where any original item is amended, voided or superseded hereby, the provisions of such items not so specifically amended, voided or superseded will remain in effect.

This addendum must be signed and attached to bid proposal to acknowledge receipt of addendum.
Failure to acknowledge any addenda will result in a non-responsive bid.

Company's Name

Date

Authorized Representative's Name

Authorized Representative's Signature

Bid #19-33

Cement Stabilized Base Reclamation Construction, Milling & Resurfacing on Various County Roads Revisions

The bid documents will be revised as follows:

A. TERMS AND CONDITIONS

1. Completion of Performance/Completion Time

- b.** Unless otherwise extended by approved Change Order(s), Contractor shall complete its performance of this contract within **one-hundred eighty (180) calendar days** from date of receipt of the written Notice to Proceed from Henry County.

SPECIAL PROVISIONS

Applying to the Standard Specification

PROJECT – Reclamation, patching, milling and resurfacing of 14 roads in Henry County

- II.** Section 301: Cement Stabilized Reclaimed Base Construction
- J.** Two lifts of asphalt will be placed throughout each entire roadway authorized for reclamation, a minimum of 5 days after cement stabilized base construction has been completed to insure proper curing. For roads A2 (Wilson) & A3 (Hemphill) the bottom lift will be 2 inches of 19mm S.P. including hydrated lime. For road A1 (Industrial Pkwy (aka Avalon Pkwy)), the bottom lift will be 3 inches of 19mm S.P. including hydrated lime. The top lift will be an inch and a half of 12.5mm S.P. including hydrated lime. All mainline mixes will require the use of an approved MTV.

Additional information regarding milling:

The turn lanes (aka decel/accel areas) adjacent to the roads are not to be reclaimed unless directed as such by the engineer. Typically, for the decel/accel areas to receive asphalt overlay (as directed by the engineer), mill the asphalt area next to the curb line of the decel/accel area to provide for flush tie in to gutter line with resurfacing. On roads to be milled and resurfaced, there is no requirement to mill/resurface onto adjoining roadways (that are not listed in the contract) beyond the mainline road's decel lane/accel taper area (or beyond the mainline road's edges of pavement when no decel/accel present). On roads to be reclaimed and resurfaced, the side roads/major driveways, where necessary, shall be milled (typically no more than 30' into the side street) in order to provide for a flush tie in to existing with the resurfacing.

Bid # 19-33
Cement Stabilized Base Reclamation Construction, Milling, Patching, and
Resurfacing on Various County Roads
Bid Price Sheet (2nd Revision)

Vendor shall furnish all materials, labor, tools, equipment and services required for Cement Stabilized Reclaimed Base Construction, Milling, Patching, and Resurfacing of approximately 11.90 miles of various county roads; complete per bid specifications.

14 Roads (approximately 12 miles) within Henry County

1 of 2

GA DOT Item No.	Description	Approx. Qty.	Units	Unit Price	Total Price
150-1000	Traffic Control (including temporary Striping)	1	L.S.	\$	\$
163-0240	Mulch	10	TN	\$	\$
171-0030	Temporary Silt Fence, Type C	600	LF	\$	\$
210-0200	Grading, Adjust shoulder to grade	3.6	LM	\$	\$
301-5000	Portland Cement	1183	TN	\$	\$
301-6000	Cement Treated Base Course	47330	SY	\$	\$
310 - 1101	Graded Aggregate Base	20	Ton	\$	\$
402-1802	Recycled Asph Conc Patching (25mm SP) incl Bitum Matl & H Lime)	650	TN	\$	\$
402-1812	Recycled Asph Conc Leveling, Incl Bitum Matl & H Lime	240	TN	\$	\$
402-3103	Recycled Asph Conc 9.5 mm superpave, Type II , incl. bitum Matl. & Hyd Lime	5250	TN	\$	\$
402-3190	Recycled Asph Conc 19 mm superpave incl. Bitum Matl. & Hyd Lime	5510	TN	\$	\$
402-3113	Recycled Asph Conc 12.5mm superpave incl. Bitum Matl. & Hyd Lime	10400	TN	\$	\$
412-1000	Bituminous Prime Coat including Sand	14200	GAL	\$	\$
413-1000	Bituminous Tack Coat	13720	GAL	\$	\$
429-1000	Rumble Strips	8	EA	\$	\$
432-5010	Mill Asphalt Concrete Pvmt, Variable Depth	124000	SY	\$	\$
441-0016	Driveway Concrete, 6" thick	100	SY	\$	\$
653-0105	Thermoplastic Mark, Symbol	2	EA	\$	\$
653-0120	Thermoplastic, solid traffic Arrow Ty 2	27	EA	\$	\$
653-0130	Thermoplastic, solid traffic Arrow Ty 3	1	EA	\$	\$
653-1501	Thermoplastic, Solid Traffic Stripe, 5" white	94550	LF	\$	\$
653-1502	Thermoplastic, Solid Traffic Stripe, 5" yellow	95130	LF	\$	\$
653-1704	Thermoplastic, Solid Traffic Stripe, 24" white (stop bar)	20	EA	\$	\$

Company's Name: _____

Bid # 19-33
Cement Stabilized Base Reclamation Construction, Milling, Patching, and
Resurfacing on Various County Roads
Bid Price Sheet (2nd Revision)

2 of 2

GA DOT Item No.	Description	Approx. Qty.	Units	Unit Price	Total Price
653-1804	Thermoplastic 8" White	140	LF	\$	\$
653-3501	Thermoplastic, Skip Traffic Stripe, 5" white	1600	GLF	\$	\$
653-3502	Thermoplastic, Skip Traffic Stripe, 5" yellow	8375	GLF	\$	\$
653-6004	Thermoplastic, Traffic Stripe, white	527	SY	\$	\$
653-6006	Thermoplastic, Traffic Stripe, yellow	71	SY	\$	\$
654-1003	Raised Pavement Markers, TP 1, 2 or 3	2600	EA	\$	\$
654-1010	Raised Pavement Markers TP 10	50	EA	\$	\$
700-6910	Permanent Grassing	5	AC	\$	\$
700-7000	Agricultural Lime	7	TN	\$	\$
700-8000	Fertilizer Mixed Grade	5	TN	\$	\$
700-8100	Fertilizer Nitrogen Content	3	LB	\$	\$
700-9300	Sod	90	SY	\$	\$
TOTAL COST					\$

Total bid amount (words): _____

Note: Completion time for this work is **one hundred eighty (180) calendar days** after receipt of written Notice to Proceed from the County; thereafter, liquidated damage charges shall be assessed at the rate of two-hundred forty seven dollars (\$247) per calendar day.

Company's Name

Date

Authorized Representative's Name (Print or Type)

Authorized Representative's Signature