



**Henry County  
Purchasing Department**  
140 Henry Parkway, McDonough, GA 30253  
Phone: 770-288-6027 Fax: 770-288-6047

**Website:** [henrycounty-ga.com/purchasing](http://henrycounty-ga.com/purchasing)

**ADDENDUM #1**  
**Issued June 23, 2020**

**Bid # 20-47**  
**Grading, Widening, and Paving of Peeksville Road**  
**Due Date and Time: June 30, 3:00 PM**

---

The following items take precedence over referenced portions of the documents for the above-named project and in executing a contract, will become a part thereof. Where any item in the documents is supplemented hereby, the original requirements will remain in effect. All supplemental conditions will be considered as added thereto. Where any original item is amended, voided or superseded hereby, the provisions of such items not so specifically amended, voided or superseded will remain in effect.

---

**REVISION:**

**The Bid Price Sheets have been revised and are included in this addendum.**

This addendum must be signed and attached to bid proposal to acknowledge receipt of addendum.  
**Failure to acknowledge any addenda will result in a non-responsive bid.**

---

Company's Name

---

Date

---

Authorized Representative's Name

---

Authorized Representative's Signature

**Bid # 20-47**  
**Grading, Widening, and Paving of Peeksville Road**  
**Questions and Answers**

1. **Question:** Could we get clarification on Line No. 0240? The Item Number 700-9300 is for SOD but calls for FERTILIZER NITROGEN CONTENT on the bid sheet?  
**Answer:** **There is no SOD item on this project. This has been corrected on the Bid Price Sheet.**
2. **Question:** Could we get a detail for Line No. 130 CNST EXIT TIRE WASH ASSY?  
**Answer:** **Please see GDOT Construction Exit Detail D-41.**
3. **Question:** The quantities in the bid form for GAB and 12.5 mm Asphalt only represent the amount needed for the roadway and do not included the quantity needed for the driveways as shown on drawing 6-001 of the plans. Will the quantities be updated on the bid sheet?  
**Answer:** **Both GAB and 12.5 MM Asphalt quantity are updated on the bid sheet.**
4. **Question:** What is the allowable road closure length, if any? Is there a detour plan that can be added to the plan set?  
**Answer:** **No road closure allowable on this project.**
5. **Question:** What are the allowable working hours?  
**Answer:** **There should be no work between 6 am to 9 am Monday through Friday.**
6. **Question:** Will prime be required for the asphalt paving?  
**Answer:** **Prime on the asphalt paving is not required.**
7. **Question:** Who will handle the material testing? Will the County hire a testing firm?  
**Answer:** **County will handle all testing related to this project.**
8. **Question:** If the Contractor cannot close Peeksville Road to construct the full depth paving, can staging plans be provided?  
**Answer:** **Staging plan will not be provided.**
9. **Question:** Is sod required on this project anywhere? If so, can a pay item be added?  
**Answer:** **Please refer to question #1.**

**Bid # 20-47**  
**Grading, Widening, and Paving of Peeksville Road**  
**Bid Price Sheet - Revised**

LINE NO.	ITEM NO.	ITEM DESCRIPTION ROADWAY	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0005	150-1000	TRAFFIC CONTROL - SP4132	LS	1		
0010	210-0100	GRADING COMPLETE -	LS	1		
0015	310-1101	GR AGGR BASE CRS, INCL MATL	TN	8,400		
0020	318-3000	AGGR SURF CRS	TN	750		
0025	402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	1,250		
0030	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1,327		
0035	413-0750	TACK COAT	GL	422		
0040	441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	51		
0045	441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	1,844		
0050	550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	228		
0055	550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	169		
0060	550-1300	STORM DRAIN PIPE, 30 IN, H 1-10	LF	79		
0065	550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	282		
0070	550-4118	FLARED END SECTION 18 IN, SIDE DRAIN	EA	18		
0075	550-4218	FLARED END SECTION 18 IN, STORM DRAIN	EA	10		
0080	550-4224	FLARED END SECTION 24 IN, STORM DRAIN	EA	6		
0085	550-4230	FLARED END SECTION 30 IN, STORM DRAIN	EA	1		
0090	603-2181	STN DUMPED RIP RAP, TP3, 18 IN	SY	313		
0095	603-7000	PLASTIC FILTER FABRIC	SY	313		
0100	634-1200	RIGHT OF WAY MARKERS	EA	69		
0105	643-8200	BARRIER FENCE (ORANGE), 4 FT	LF	422		
0110	668-2100	DROP INLET, GP 1	EA	1		
<b>SUBTOTAL (ROADWAY)</b>						

**Company's Name:** \_\_\_\_\_

**Bid # 20-47**  
**Grading, Widening, and Paving of Peeksville Road**  
**Bid Price Sheet - Revised**

LINE NO.	ITEM NO.	ITEM DESCRIPTION PERMANENT EROSION	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0115	163-0232	TEMPORARY GRASSING	AC	4		
0120	163-0240	MULCH	TN	125		
0125	163-0300	CONSTRUCTION EXIT	EA	3		
0130	163-0310	CNST EXIT TIRE WASH ASSY	EA	3		
0135	163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	18		
0140	163-0520	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	49		
0145	163-0527	CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	EA	146		
0150	163-0539	CONSTRUCT AND REMOVE RETROFIT-SLOTTED BOARD DAM W/STONE FILTER	EA	16		
0155	163-0541	CONSTRUCT AND REMOVE ROCK FILTER DAMS	EA	10		
0160	163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	1		
0165	165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	4,097		
0170	165-0041	MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	2,190		
0175	165-0087	MAINTENANCE OF SILT CONTROL GATE, TP3	EA	18		
0180	165-0096	MAINTENANCE OF RETROFIT-SLOTTED BOARD DAM W/STONE FILTER	EA	16		
0185	165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	3		
0190	165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	1		
0195	165-0110	MAINTENANCE OF ROCK FILTER DAM	EA	10		
0200	165-0310	MAINTENACE OF CNST EXIT TIRE WASH ASSY	EA	3		
0205	167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	3		
0210	167-1500	WATER QUALITY INSPECTIONS	MO	12		
0215	171-0030	TEMPORARY SILT FENCE, TYPE C	LF	8,193		
0220	700-6910	PERMANENT GRASSING	AC	8		
0225	700-7000	AGRICULTURAL LIME	TN	24		
0230	700-8000	FERTILZER MIXED GRADE	TN	8		
0235	700-8100	FERTILZER NITROGEN CONTENT	LB	400		
0240	716-2000	EROSION CONTROL MATS, SLOPES	SY	11,582		
<b>SUBTOTAL (PERMANENT EROSION CONTROL)</b>						

**Company's Name:** \_\_\_\_\_

**Bid # 20-47**  
**Grading, Widening, and Paving of Peeksville Road**  
**Bid Price Sheet - Revised**

LINE NO.	ITEM NO.	ITEM DESCRIPTION SIGNING AND MARKING	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0245	636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	14		
0250	636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	25		
0255	636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	SF	105		
0260	636-2070	GALV STEEL POSTS, TP 7	LF	207		
0265	653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	8,801		
0270	653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	8,759		
0275	653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	76		
0280	654-1001	RAISED PVMT MARKERS TP 1	EA	224		
<b>SUBTOTAL (SIGNING AND MARKING)</b>						
<b>TOTAL BID AMOUNT</b>						

**TOTAL BID AMOUNT (WORDS):** \_\_\_\_\_

**Company's Name:** \_\_\_\_\_ **Date:** \_\_\_\_\_

\_\_\_\_\_  
**Authorized Representative's Name (Print or Type)**

\_\_\_\_\_  
**Authorized Representative's Signature**