



**Henry County  
Purchasing Department**  
140 Henry Parkway, McDonough, GA 30253  
Phone: 770-288-6027 Fax: 770-288-6047

**Website:** [henrycounty-ga.com/purchasing](http://henrycounty-ga.com/purchasing)

**ADDENDUM #1**  
**Issued June 24, 2020**

**Bid # 21-03**  
**Speer Road Storm Drain Repair**  
**Due Date and Time: July 1, 2020, 3:00 PM**

---

The following items take precedence over referenced portions of the documents for the above-named project and in executing a contract, will become a part thereof. Where any item in the documents is supplemented hereby, the original requirements will remain in effect. All supplemental conditions will be considered as added thereto. Where any original item is amended, voided or superseded hereby, the provisions of such items not so specifically amended, voided or superseded will remain in effect.

---

**REVISIONS:**

**Contractor shall coordinate with utility companies in their relocation.**

**SECTION II – SPECIFICATIONS (Page 13)**

**2. Date of Commencement and Substantial Completion**

- b. The Contractor shall achieve Substantial Completion of the entire Work not later than **30 one hundred twenty (120)** calendar days after receipt of Notice to Proceed subject to adjustments of this Contract Time as provided in the Contract Documents.

**The Bid Price Sheets included with this addendum have been revised and will replace the previous bid price sheets.**

This addendum must be signed and attached to bid proposal to acknowledge receipt of addendum.  
**Failure to acknowledge any addenda will result in a non-responsive bid.**

\_\_\_\_\_  
Company's Name

\_\_\_\_\_  
Date

\_\_\_\_\_  
Authorized Representative's Name

\_\_\_\_\_  
Authorized Representative's Signature

**Bid # 21-03**  
**Speer Road Storm Drain Repair**  
**Questions and Answers**

1. **Question:** Will Henry County accept a Precast Concrete Box Culvert Option in lieu of a Cast-in-place culvert for this project?  
**Answer:** **This will be considered after bid. Need to make sure that will not be a utility conflict with a cast in place.**
2. **Question:** Is the unit of measure for line item No.0035 – Class AA Concrete correct? Typically, this item would be paid as a cubic yard (CY) measurement.  
**Answer:** **The Bid Price Sheet has been revised to show the unit of measure as CY.**
3. **Question:** Could you please tell me if Construction Details and Typical Sections will be published for this project?  
**Answer:** **Construction details are provided in the plan set. The pavement patching section is provided on the plans as well. Typical sections are not provided since only the culvert is being replaced.**
4. **Question:** What will allowable lane closure hours be for this project?  
**Answer:** **There are no individual lane closures. All lanes will be closed.**
5. **Question:** Can we use pre cast box and headwall? If so, would require shop drawing submittal to justify the quantities of steel and concrete?  
**Answer:** **Please refer to Question #1.**
6. **Question:** Can Precast Box culvert sections be used instead of CIP?  
**Answer:** **Please refer to Question #1.**
7. **Question:** Has all Right of Entries, permits been acquired?  
**Answer:** **We are still working in acquiring the right of way.**
8. **Question:** Who will be paying for the required testing?  
**Answer:** **The County will perform soil and concrete tests.**
9. **Question:** Is there any bore testing samples?  
**Answer:** **There are no bore samples.**
10. **Question:** How will rock be handled if encountered?  
**Answer:** **Contractor shall be responsible of removing any rock encountered. There shall be no additional payment if rock is encountered. Cost shall be included in the overall Grading Complete line item.**
11. **Question:** There is no line item for traffic control, is this to be included within?  
**Answer:** **Traffic Control line item has been added to the revised bid price sheet. In addition, the contractor shall be responsible to include Variable Message Boards and provide a detour plan. Cost shall be included in the overall Traffic Control line item.**

**Bid #21-03**  
**Speer Road Storm Drain Repair**  
**Bid Price Sheet Revised**

LINE #	ITEM #	ROADWAY	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0005	150-1000	TRAFFIC CONTROL	LS	1		
0010	207-0203	FOUND BK FILL MATL, TP II	CY	132		
0015	210-0100	GRADING COMPLETE	LS	1		
0020	310-1101	GR AGGR BASE CRS, INCL MATL	TN	160		
0025	402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2 ONLY, INCL BITUM MATL & H LIME	TN	30		
0030	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2 ONLY, INCL BITUM MATL & H LIME	TN	60		
0035	413-0750	TACK COAT	GL	150		
0040	500-3002	CLASS AA CONCRETE	CY	534		
0045	511-1000	BAR REINF STEEL	LB	58,712		
0050	670-0001	TEMPORARY BRACING FOR WATER LINE	LF	300		
0055	670-0002	TEMPORARY BRACING FOR SEWER	LF	300		
<b>SUBTOTAL (ROADWAY)</b>						
LINE #	ITEM #	TEMPORARY EROSION CONTROL	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0060	163-0232	TEMPORARY GRASSING	AC	0.5		
0065	163-0240	MULCH	TN	2		
0070	163-0300	CONSTRUCTION EXIT	EA	2		
0075	163-0541	CONSTRUCT AND REMOVE ROCK FILTER DAM	EA	1		
0080	165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	290		
0085	165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	2		
0090	165-0101	MAINTENANCE OF ROCK FILTER DAM	EA	1		
0095	171-0010	TEMPORARY SILT FENCE, TYPE C	LF	290		
<b>SUBTOTAL (TEMPORARY EROSION CONTROL)</b>						

Company's Name: \_\_\_\_\_

**Bid #21-03  
Speer Road Storm Drain Repair  
Bid Price Sheet Revised**

LINE #	ITEM #	PERMANENT EROSION CONTROL	UNITS	QTY.	UNIT PRICE	EXTENDED PRICE
0100	603-2180	STN DUMPED RIP RAP, TP 3, 12 IN	SY	72		
0105	603-7000	PLASTIC FILTER FABRIC	SY	72		
0110	700-6910	PERMANENT GRASSING	AC	0.5		
0115	700-7000	AGRICULTURAL LIME	TN	1.3		
0120	700-8000	FERTILIZER MIXED GRADE	TN	0.5		
0125	716-2000	EROSION CONTROL MATS, SLOPES	SY	950		
<b>SUBTOTAL (EROSION CONTROL)</b>						
<b>TOTAL BID AMOUNT</b>						

**TOTAL BID AMOUNT (WORDS):** \_\_\_\_\_

**Company's Name:** \_\_\_\_\_ **Date:** \_\_\_\_\_

\_\_\_\_\_  
**Authorized Representative's Name (Print or Type)**

\_\_\_\_\_  
**Authorized Representative's Signature**