

ROADWAY QUANTITIES

PAY ITEM NUMBER	TRAFFIC CONTROL	GRADING COMPLETE	GR AGGR BASE CRS, INCL MATL (165 lb/cf)	AGGR SURF CRS	RECYC 1.5" ASP CON 12.5MM CONC SUPERPAVE	DRIVEWAY CONCRETE, 6 IN TK	CONC VALLEY GUTTER, 6 IN	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	GALV STEEL POSTS, TP 7	PAVEMENT ALTERNATIVES	GR AGGR BASE CRS, INCL MATL (165 lb/cf)	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL	SURFACE TREATMENT	SOLID TRAFFIC STRIPE, 5 IN, WHITE	SOLID TRAFFIC STRIPE, 5 IN, YELLOW	SOLID TRAFFIC STRIPE, 24 IN, WHITE	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	RAISED PYMT MARKERS TP 2
	LS	LS	TN	TN	TN	SY	SY	SF	SF	LF		TN	TN	SY	LF	LF	LF	LF	LF	LF	LF
1	1	1	1982		420	248	70	30	173	318	Alt A	26906	5979	0	0	0	0	37255	37035	84	612
											Alt B	26906	0	54355	37255	37035	84	0	0	0	0
											Alt C	26906	3012	26982	18482	18501	32	18773	18534	52	324
Note - Henry Co. to select alternative after bids are submitted. Alt A - 8" GAB, 2" Surface Course Alt B - 8" GAB, Surface Treatment Alt C - Bill Gardner Pkwy to Frog Rd - 8" GAB, 2" Surface Course Frog Rd to Indian Creek - 8" GAB, Surface Treatment Indian Creek to L.G. Griffin Rd - 8" GAB, 2" Surface Course																					
SUBTOTAL	1	1	1982	0	420	248	70	30	173	318											
DIRECTED BY ENGINEER	0	0	199	1000	42	25	7	3	18	32											
TOTAL	1	1	2181	1000	462	273	77	33	191	350											

FENCE QUANTITIES

	RESET GATE	CH LK FENCE, ZC COAT, 6 FT, 11 GA	WOVEN WIRE FENCE	BARBED WIRE FENCE, 4 STRAND	BARBED WIRE FENCE, 5 STRAND
PAY ITEM NUMBER	611-4996	643-1153	643-4000	643-8104	643-8105
	EA	LF	LF	LF	LF
Parcel 9	1		212		
Parcel 29		106			
Parcel 30				164	
Parcel 31	1				2618
Parcel 32	2			950	
Parcel 36				250	
Parcel 38				680	
Parcel 39	1				
Parcel 40	2	278			
Parcel 41			1790		
Parcel 42			440		
Parcel 46	1		14		
Parcel 48			16		
Parcel 50			55		
Parcel 53			450		
Parcel 55			470	470	
Parcel 57	1		530	530	
Parcel 59	1		520	520	
Parcel 62			800	800	
SUBTOTAL	10	384	5297	4364	2618
DIRECTED BY ENGINEER	1	39	529	437	262
TOTAL	11	423	5826	4801	2880

EROSION CONTROL QUANTITIES

PAY ITEM NUMBER	TEMPORARY GRASSING	MULCH	CONSTRUCTION EXIT	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	CONSTRUCT AND REMOVE FABRIC CHECK DAMS	CONSTRUCT AND REMOVE SEDIMENT BASIN, TP 1	CONSTRUCT AND REMOVE ROCK FILTER DAMS	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	MAINTENANCE OF CHECK DAMS - ALL TYPES	MAINTENANCE OF TEMPORARY SEDIMENT BASIN	MAINTENANCE OF SILT CONTROL GATE, TP 3	MAINTENANCE OF CONSTRUCTION EXIT	MAINTENANCE OF ROCK FILTER DAM	WATER QUALITY MONITORING AND SAMPLING	WATER QUALITY INSPECTIONS	TEMPORARY SILT FENCE, TYPE C	PERMANENT GRASSING	AGRICULTURAL LIME	FERTILIZER MIXED GRAD	FERTILIZER NITROGEN CONTENT
	AC	TN	EA	EA	LF	EA	EA	LF	LF	EA	EA	EA	EA	EA	MO	LF	AC	TN	TN	LB
10	868	5	14	23257		75	19355	11629			7	5	38	2	18	38709	23	46	5	1150
SUBTOTAL	10	868	5	14	23257	0	75	19355	11629	0	7	5	38	2	18	38709	23	46	5	1150
DIRECTED BY ENGINEER	5	87	1	2	2326	1	8	1936	1163	1	1	1	4	1	6	3871	3	5	1	115
TOTAL	15	955	6	16	25583	1	83	21291	12792	1	8	6	42	3	24	42580	26	51	6	1265



REVISION DATES	
10/10/16	

HENRY COUNTY
DEPARTMENT OF TRANSPORTATION
OFFICE: SPOST/DEPARTMENT OF TRANSPORTATION
SUMMARY QUANTITIES
RECONSTRUCTION AND PAVING
LESTER MILL RD.